

Production Monthly Performance Update



LINIT 1 PASSENGER
FLEVATOR

See Company Marie 1

Page 112

NPPD Board of Directors Meeting

Operations Committee

November 2025

Art Wiese - Vice President, Energy Production



Gerald Gentleman Station



- Unit 1: Forced derate on 9/22-23 due to loss of reservoir pump.
 Operated per market dispatch remainder of September through October.
- **Unit 2:** Maintenance outage on 9/7 to replace FD fan rotor, returned on 9/11. Operated per market dispatch remainder of September through October.



- ✓ Unit 1 began operation in 1979 665 MW
- ✓ Unit 2 began operation in 1982 700 MW

Gerald Gentleman Station




 Slope Tube Leak on Unit 1, repaired during Maintenance outage Nov. 2-4, 2025:





Gerald Gentleman Station




Hallam


- **Unit 1:** Forced derate on 9/3 due to damper on cyclone; again on 9/22 due to furnace pressure issues. Forced outage on 9/5 due to tube leaked, returned on 9/12. Forced derate on 10/15 due to furnace pressure issues. Maintenance outage began on 10/17 due to maintenance margin available start planned fall outage 1 week early.
- **Unit 2:** Forced derate on 9/22 due to furnace pressure issues. Operated per market dispatch remainder of September. Planned outage began on 10/6.



- ✓ Constructed between 1958 and 1963
- ✓ Nuclear portion decommissioned in 1964 then converted to coal and gas-fired boiler
- ✓ Unit 1 began operation in 1961 (105 MW) / Unit 2 began operation in 1968 (120 MW)
- ✓ Combined: 225 MW


Outage Photos - Unit 2 Reheater









Outage Photos - Unit 2 Reheater









Canaday Station

Significant Operating Events

Fall maintenance outage began on 9/29.






- ✓ Purchased by NPPD in 1995
- ✓ Restarted facility in 1998
- √ 100 MW



Canaday Station



Beatrice Power Station



- Planned fall outage began on 9/20 and ended early on 10/9.
- Forced derate on 10/17 due to fuel system issues leading to a forced outage taken on 10/18, issue was resolved same day.




- ✓ Completed in 2005
- √250 MW
 - 80 MW each for Combustion Turbine
 - 90 MW for Steam Turbine

Beatrice Power Station

Capacity & Equivalent Availability Factors

October 2025



Ainsworth Wind Turbines




- As of Nov 5th, there were two (2) turbines offline:
 - ✓ One for pitch main pump motor issues (sourcing materials)
 - ✓ One shut off due to pitch cylinder leak (material on order)
- Blade tip repair completed for the year.



- ✓ NPPD Owned
- ✓ Commercial Operation: December 2005
- ✓ 60 MW total / NPPD Share: 32 MW
- ✓ 36 turbines
- √ 1.65 MW each
- ✓ Turbine blades 131 ft. long, tubular towers stand 230 ft. high

Ainsworth Wind Turbines







PPA Wind Farm

Capacity Factor (average all combined)






NORTH HUB FLIPS TO PREMIUM HUB IN OCTOBER, LMP UP \$10 Y/Y



- Significant negative congestion seen in October, with DA LMPs falling \$5.69 below the DA MEC
- DART spread flips back to positive as we enter Fall
- Cash Henry Hub traded flat throughout the entire summer, averaging \$3.09 Apr-Oct
- Wind generation gaps up over 3 GW month-over month



NPPD's Generation Profile



LEGEND

NPPD Owned

Power Purchase Agreement (All or Part)

Retail Community Solar Locations